

Master Services Agreement & Field Dispatch Schedule

Confidential — Supplier Agreement (RALA) | MSA-2026-PO-0291 | Rev B | Effective 2026-02-15 – 2028-02-14

1. Parties & Supplier Overview

Supplier (legal name)	Pacific OptoLink Networks, Inc.
Vendor ID	VND-PO-0291
Service territory	Wenatchee East, Quincy South, Columbia Basin DWDM Ring
Specialties	DWDM line-system commissioning, ROADM provisioning, coherent optics turn-up, OS2 single-mode splicing, MPO-16 / MPO-24 trunk certification
After-hours dispatch	+1-206-555-0188 · noc@pacificoptolink.example
Governing region	US West / Columbia Basin

2. Certificate of Insurance (COI)

Carrier	Cascadia Casualty Group
Policy number	COI-PO-77204
General liability	\$3,000,000
Professional liability	\$2,000,000
Workers' comp	Statutory — WA L&I; compliant
Additional insured	Microsoft Corporation and affiliates
Expiration	2027-01-31

3. Rate Card

Code	Description	Unit	Rate (USD)	Min
LBR-STD	Standard labor — business hours (M-F 06:00-18:00)	per hour	\$158.00	2
LBR-AH	After-hours / weekend labor	per hour	\$265.00	3
LBR-P1	P1 emergency dispatch (≤90m response)	per hour	\$345.00	4
DWDM-TURN	DWDM channel turn-up & power balancing	per channel	\$92.00	1
ROADM-PROV	ROADM degree provisioning & validation	per degree	\$480.00	1

Code	Description	Unit	Rate (USD)	Min
MPO-CERT	MPO-16/24 polarity + loss certification	per trunk	\$74.00	1

4. Service Level Agreement

Priority	Ack (min)	On-site (hrs)	Credit if missed
P1 - Critical	10	1.5	20%
P2 - High	30	6	10%
P3 - Normal	90	36	5%

Monthly availability target: **99.95%** · Max loss budget: **2.2 dB**

5. Safety Attestation

OSHA 300A on file	Yes
EMR rating	0.69
Required PPE	ESD wrist strap, Eye protection (laser-rated, Class 1M), Cut-resistant gloves, Arc-flash kit for power-adjacent work
Certifications	BICSI Installer 2 (Optical), CFOS/D (DWDM specialty), CFOT (Certified Fiber Optic Technician), OSHA 10, First Aid / CPR
Last safety audit	2026-04-02 — Pass — one advisory (laser signage refresh)

6. Dispatch Quick Reference

Site	Wenatchee East D-side
Preferred connector	LC/APC Duplex
Trunk type	MPO-16
Spare locker	Cage locker D-1
Escalation path	Network Dispatch → Pacific OptoLink NOC Lead → Microsoft Site Reliability On-Call
Notes	D-side runs APC end-faces on the DWDM line system — do NOT mate with UPC patch cords. Verify return loss > 60 dB before turn-up.